

SURVEY &
REMONUMENTATION

4577

OCT 05 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>1W</u>	<u>M-1</u>
	T <u>23N</u> R <u>1W</u>	<u>M-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

8 JUN 98 10:11 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on 4-29, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-1 GLO - 1838 L. Clason, D.S. L.1, Pg. 290 Oct 28, 1982 K.J. Ostling, P.S. #10068
 Mon. - Post Found 1 1/2" Pipe with concrete base, by M. Schaaf
 14" Y. Pine N42°E 49 lks in line with firelines N. & W. and fence S.
 16" Y. Pine S22°E 181 lks 12" Red Oak N37°E 18.8'
 7" Black Oak N30°W 28.4'
 Fence Corner S10°E 2.5'

ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE MAY 15, 1998

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron in centerline fence intersection to the South and East. Found GLO. witnesses; Y. Pine stump N42°E 32.3', and Y. pine stump S22°E 119.4'. Iron matches GLO witnesses.

- Found nail with Roscommon tag in the NW. side of a 16" R. Oak N30°E 19.51'
- Found nail with Roscommon tag in the NW. side of a 8" B. Oak N36°W 28.58'
- Found nail with Roscommon tag in the NW. side of a 10" W. Oak S58°W 51.90'
- Found nail with Roscommon tag in the NW. side of a 10" S40°E 45.62'
- Found GLO Y. Pine stump N42°E 32.3'
- Found GLO Y. Pine stump S22°E 119.4'

Accepted as a perpetuation of the Original Government Corner. Replaced 1/2" iron with Standard County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Standard Roscommon County Monument.

- Wit: Found nail with Roscommon tag in the NW. side of a 16" R. Oak N30°E 19.51'
- Found nail with Roscommon tag in the NW. side of a 8" B. Oak N36°W 28.58'
- Found nail with Roscommon tag in the NW. side of a 10" W. Oak S58°W 51.90'
- Found nail with Roscommon tag in the NW. side of a 10" S40°E 45.62'

Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date JUNE 4TH 1998



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1971
REVISED JAN. 1974
REVISED OCT., 1974

LIBER 3 PAGE 526