

**SURVEY &
REMONUMENTATION**

OCT 05 1998

4579

SECTION

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

8 JUN 98 10:11 A.M.

For corners in

Roscommon
(County)

Located In:

Corner Code #

ROBERT W. SMITH
REGISTER OF DEEDS

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>22N</u> R <u>1W</u> | <u>M-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on 4-23, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-3 GLO - 1838 Lewis Clason, D.S.
Mon. - Post
13" White Oak S59°W 48 fks.
16" Y. Pine N23°W 109 fks.
GLO - 1846 B.F. Hall, D.S.
Mon - Post
Wit: 18" Y. Pine N83°E 17 fks
18" Y. Pine S46°E 81 fks
L. 6, Pg. 147 (Timothy, L. Lapham, P.S. #27595 Nov. 23, 1988)
Mon. - 1 1/2" pipe in concrete in N-S fence line, and Firelane West.
Nails & Tags in:
10" R. Pine N50°W 38.05'
12" R. Pine S25°W 110.47'
12" Oak S75°E 43.08'

**RUSCOMMON COUNTY
PEER GROUP APPROVAL**

DATE May 15, 1998
Marvin E. Myers
**Marvin E. Myers, P.S.
County Surveyor**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" pipe with cap (Paul B. Lapham, P.S. #9433), 0.8' East of North-South fence, and Centerline of trail to the West.
Found nail in the NW. side of a 16" Red Pine (placed new nail directly above) S20°W 110.54'. Found nail and Lapham tag in the NE. side of a 12" Red Pine N60°W 38.11'. Found nail in the SW. side of a 12" dead Oak S73°E 43.10'. Accepted as best available evidence of the position of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon.- Standard Roscommon County Monument.
Wit: Found nail in the NW. side of a 16" Red Pine (placed new nail directly above) S20°W 110.54'
Found nail and Lapham tag in the NE. side of a 12" Red Pine N60°W 38.11'
Found nail in the SW. side of a 12" dead Oak S73°E 43.10'
Set nail in the SW. side of a 18" Oak S40°E 59.48'
Set nail in the SE. side of a 4" Red Pine N31°E 46.29'

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date June 4, 1998



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 23, 1971
REVISED MAY 14, 1978
REVISED JAN., 1983
REVISED OCT., 1995