

**SURVEY &
REMONUMENTATION**

OCT 05 1998

SECTION

4580

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

8 JUN 98 10:11 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

For corners in

Roscommon
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>22N</u> R <u>1W</u> | <u>M-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on 4-23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-4 GLO - 1838 Lewis Clason, D.S.
Mon. - Post
14" Y. Pine S55°W 80 lks.
16" Y. Pine N60°W 61 lks.

L. 2, Pg. 155
Mon. - 1/2" bar
18" Pine Stump S55°W 53.48'
15" Pine Stump N60°W 41.12'
12" Oak N80°W 42.73'
6" Oak S65°E 31.71'

L. 1, Pg. 114 (Norman C. Caldwell,
P.S. # 12018 4-18-1966)
Mon. - 1 1/2" Pipe in conc. Raised with 1/2" bar.
In N-S fence line. Found original Gov. Bearing trees
18" Pine Stump S55°W 53.48'
15" Pine Stump N60°W 41.12'
12" Oak N80°W 42.73'
6" Oak S65°E 31.71'

L. 6, Pg. 147 (Timothy, L. Lapham, P.S. #27595 Nov. 23, 1968)
Mon. - Found 1/2" Rod in Fence
Spike in Fence Post South 3.70'
10" Oak S20°E 38.45'
12" Oak N20°E 48.15'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron over 1 1/4" Pipe in concrete (typical Schaaf monument) in North-South fence and in center of old North-South road corridor. Accepted as a perpetuation of the Original Government Corner. Replaced 1/2" bar with Standard County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Standard Roscommon County Monument.
Set nail in the E. side of the Southerly 6" twin Red Pine N49°W 38.18'
Set nail in the SE. side of a 20" Oak N35°E 48.06'
Set nail in a 18" Oak S29°E 38.51'
Set nail in the S. side 4" Oak S86°E 25.80'

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE May 15, 1998**

Marvin E. Myers
**Marvin E. Myers, P.S.
County Surveyor**

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600



Date June 4th 1998