

SURVEY &
REMONUMENTATION

OCT 05 1998

SECTION

4582

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

8 JUN 98 10:12 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

For corners in

Roscommon
(County)

Located In:

Corner Code #

1. Public Land Survey

T 22N R 1W

M-6

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on 4-23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6 GLO - 1837 John Brink, D.S.
Mon. - Post
10" Black Oak S43°W 32 lks.
11" Y. Pine N20°W 57 lks.

L. 1, Pg. 117 (Norman C. Caldwell,
P.S. #12018 4-18-1966)
Mon. - Found remains of 3"X3" stake 1' East of N-S fence. Set 2" bar.
13" Oak S35°E 23.70'
16" Oak N50°E 47.45'
15" Oak S39°W 67.17'
11" W. Oak N39°W 37.69'

L. 1, Pg. 35 (Larry L. Cavanagh
P.S. #17814 April 3, 1973)
Mon. - Found 5/8" bar
12" B. Oak S25°E 23.68'
12" B. Oak N50°E 47.47'
8" W. Oak N23°W 37.66'

L. 2, Pg. 156
Mon. - 2" bar
13" Oak S35°E 23.70'
16" Oak N50°E 47.45'
15" Oak S39°W 67.17'
11" W. Oak N39°W 37.69'

L. 3, Pg. 357 (R. Higgins, P.S. 21570
April 27, 1982)
Mon - Not Given
Wit: None given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" iron inside 2" Pipe, 0.5' East of North-South fence, and in center of old North-South road corridor. Accepted as the best available evidence of the position of the Original Government Corner. Replaced 5/8" iron with Standard County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Standard Roscommon County Monument.
Set nail in the NE. side of a 18" White Oak N39°W 38.02'
Set nail in the N. side of a 10" White Oak N76°W 30.00'
Set nail in the S. side of a 14" White Oak S67°E 26.83'
Set nail in the S. side of a 14" Black Oak N80°E 37.18'

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE May 15th 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600



Date June 5 1998

LIBER 3 PAGE 521