

**SURVEY &
REMONUMENTATION**

OCT 05 1998

SECTION

4584

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

8 JUN 98 10:12 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

For corners in

Roscommon

(County)

Located In:

Corner Code #

1. Public Land Survey

T 22N R 1W

M-8

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____

S _____

S _____

S _____

3. Miscellaneous
Property in Sec.

S _____

S _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on 3-26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-8 GLO - 1837 John Brink, D.S.
Mon. - Post
16" Yellow Pine N45°W 125 lts.
16" Yellow Pine S13°W 52 lts.

Schaaf (RLS) 1930±
Found, or established and replaced

L. 1, Pg. 35 (Larry L. Cavanagh
P.S. #17614 April 3, 1973)
Mon. - Found 1/2" bar
6" Maple S45°E 33.75'
7" Maple West 8.1'
6" W. Oak N25°E 51.7'

J. Richardson (RLS)
Mon. - Found one Gov. Bt. and two
pits. Stain at corner well defined
set 1/2"x26" iron & wood marker.
7" B. Oak S82°W 8.2'
7" W. Oak S61°E 33.7'
8" W. Oak N21°E 51.68'

Robert L. Higgins (P.S. #21570) Nov. 10, 1978
Timothy L. Lapham (27595) Apr. 15, 1997
Mon. - Found 1/2" bar
6" Maple S45°E 35.75'
7" Maple West 8.1'
6" W. Oak N25°E 51.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Iron of record. Witnesses of record have been destroyed. Found nail in the NE. side of a 12" Oak N33°W 18.58'
Found nail in the W. side of a 4" Oak S19°W 14.44'. Found nail in the N. side of a 3" Maple S73°W 24.98'. Accepted as the best available evidence of the position of the Original Government Corner. Replaced 1/2" iron with Standard County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Standard Roscommon County Monument.
Found nail in the NE. side of a 12" Oak N33°W 18.58'
Found nail in the W. side of a 4" Oak S19°W 14.44'
Found nail in the N. side of a 3" Maple S73°W 24.98'
Set nail in the E. side of a 8" Oak N04°E 49.94'

**ROSCOMMON COUNTY
PEER GROUP APPROVAL**

DATE MAY 15TH 1998

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor

Date JUN 5TH 1998

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 34600



APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 19
REVISED MAY 14, 19
REVISED JAN. 19
REVISED OCT., 19

1000 3 PALE 533