

**SURVEY &  
REMONUMENTATION**

OCT 05 1998

SECTION

4585

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Roscommon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>1W</u>	<u>M-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

8 JUN 98 10:12 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on 3-26, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

<b>M-9</b>	GLO - 1837 J. Brink, D.S. Mon. - Post 16" Yellow Pine N25°W 53 lks. 14" Yellow Pine S75°W 83 lks. GLO - 1846 B. F. Hall, D.S. Mon. - Post Wit: 36" Y. Pine N17°E 72 lks 35" W. Pine S79 1/2°E 73 lks	George D. Henning RLS #2240 May 1967 Mon - 1/2" bar in Center of Roads set from Orig. U.S. Witnesses. 5" W. Oak N45°W 46.4' 6" B. Oak N38°E 47.9' 8" R. Oak S47°E 64.8'	L. 2, Pg. 185 (Timothy L. Lapham P.S. #27595 July, 29 1992 & Mar. 15, 1997) Mon. - Found 1/2" iron of record 12" Oak S40°E 25.73' 6" Oak S80°E 46.33' 14" Oak N10°W 34.00' 14" Oak N75°W 26.47'
	<b>M. Schaaf, RLS</b> Found or established, & replaced George D. Henning RLS# 2240 July 13, 1976 Mon.- 1 1/2" bar in center of roads set from orig. U.S. witnesses 5" W. Oak N45°W 46.4' 6" B. Oak N38°E 47.9' 8" R. Oak S47°E 64.8'	Robert Higgins, P.S. #21570 Nov. 10, 1978 Mon.- Found 1/2" iron 5" W. Oak N45°W 46.4' 6" B. Oak N38°E 47.9' 8" R. Oak S47°E 64.8'	L. 6, Pg. 9 (Duane F. Ledy P.S. #21575 12-1-94) Mon. - Found 1/2" Rod @ Int. of 2-Track Rds. Spikes in: 14" Oak N55°E 79.57' Stump S80°E 48.29' 12" Oak North 34.19' 18" Oak N45°W 26.72'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
Found 1/2" Iron in centerline of trail roads to the East, West, South, and S72°W. Found nail in the W. side of a 12" Oak N05°W 33.97'. Found nail in the N. side of a 18" Oak N70°E 79.63'. Found nail in the S. side of a 8" Oak S76°E 46.33'. Found nail in the NE. side of a 16" Oak N68°W 26.49'. Accepted as a perpetuation of the Original Government Corner. Replaced with Standard County Monument.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
Mon.- Standard Roscommon County Monument.  
Found nail in the W. side of a 12" Oak N05°W 33.97'  
Found nail in the N. side of a 18" Oak N70°E 79.63'  
Found nail in the S. side of a 8" Oak S76°E 46.33'  
Found nail in the NE. side of a 16" Oak N68°W 26.49'

**ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE MAY 15<sup>th</sup> 1998**

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

Date June 5<sup>th</sup> 1998

Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

