

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>22</u> N. <u>2</u> R. <u>2</u> W.	C-10; C-11; D-11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 8, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 10 Found squared, scribed post at corner, and pine stump NBT easterly, as established by unknown surveyor, although scribing resembles that of E. L. Houghton.
- 11 Set corner by double proportionate measurement between corners 1 mile east and west, and ½ mile north and south. Found squared post remains lying down, about 25' W'ly but were unable to locate bottom and cannot positively verify its validity.
- 11 Set corner by single proportionate measurement between section corners. Can find nothing for previous corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10	C-11	D-11
Set ½"x18" iron bar	Set DNR mon. & cedar post	Set DNR monument
12" B. Oak N81°E 43.7	7" Cedar N26°E 46.8	10" R. Pine S09°E 79.5
10" B. Oak S12°W 84.6	6" Cedar S24°W 50.9	9" S. Maple S77°W 69.2
	6" Y. Birch N78°W 25.6	

SIGNED BY *Kenneth J. Ostling* DATE 12/8/77
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ ROSCOMMON COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET