

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Roscommon (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>31</u> T <u>22N</u> R <u>2W</u>	<u>14</u>
	S <u>31</u> T <u>22N</u> R <u>2W</u>	<u>13</u>
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on January 15, 2008 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

13- Russell A. Cavanagh P.S. #46657 set a 1/2" bar with P.S. cap #46657 for this corner while doing a survey in the area.

14- Russell A. Cavanagh P.S. #46657 set a 1/2" bar with P.S. cap #46657 for this corner while doing a survey in the area.

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

13- Found 1/2" bar with P.S. cap #46657

14- Found 1/2" bar with P.S. cap #46657

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

13- Drove 1" X 48" pipe over found 1/2" bar  
 Wit: Set nail and tag in south side of a 8" Cedar N82°W 13.72'  
 Set nail and tag in East side of a 10" Maple N06°E 15.84'  
 Set nail and tag in East side of a 8' Cedar S29°W 19.95'  
 Set nail and tag in Southwest side of 8" Cedar S45°E 31.30'  
 Carsonite post North 1'

14- Drove 1" X 48" pipe over found 1/2" bar  
 Wit: Set nail and tag in Northeast side of a 5" Cedar N42°W 8.33'  
 Set nail and tag in North side of a 8" Tamarack S60°E 12.84'  
 Set nail and tag in East side of a 6" Cedar S05°W 19.76'  
 Set nail and tag in East side of a 7" Cedar N09°E 14.71'  
 Carsonite post North 1'±

Signed by: Carl T. Kiiskila  
 Surveyor's Michigan License No.: 33981

Date: 2-6-08

