

8347 SURVEY & REMONUMENTATION

ROSCOMMON COUNTY REMONUMENTATION TO BE FILED IN LIBER 3 OF LAND CORNERS

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in

Roscommon
(County)

COMMISSION

Located In:

Corner Code #

14 NOV 94 3:06 P.M.

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>22N</u> R <u>2W</u> | <u>A-8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

ROBERT W. SMITH
REGISTER OF DEEDS
ROSCOMMON COUNTY

PEER GROUP APPROVAL

DATE 5-20-94 MEM

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey on September, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 Post set by John Burt 1838 1980 Survey, L. Cavanagh, Liber 377, Pages 235-263
 Tamarack 8" S65°W 5 links 7" Cedar S65°W 12.4'
 Cedar 6" N20°W 7 links 5" Cedar S90°E 7.8'
 5" Cedar N80°E 14.9'
 5" Cedar N30°W 3.95'
 Unrecorded DNR Plat indicates reset by Schaaf
 1980 Cavanagh, LCRC
 Liber 1, Page 196
 Same Wit.
 1973 LCRC, L. Cavanagh (list first 3 wit as below)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 2" pipe in concrete (Schaaf)
 Found 3 of the 1980 Witnesses

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 1/2" x 24" cast iron Roscommon County Monument
 S50°E nail and tag in face of Blaze 5" Cedar 7.8'
 N80°E nail and tag in face of Blaze 5" Cedar 15.02'
 N30°W nail and tag in face of Blaze 5" Cedar 3.95'
 S60°W nail and tag in 7" Tamarack 6.7'

Is accepted as the best available evidence of the position of the original corner.

Signed by Larry L. Cavanagh Date 11/19/94
 Surveyor's Michigan License No. 17614



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

LIBER 3 PAGE 128