

8349 SURVEY & REMONUMENTATION

ROSCOMMON COUNTY REMONUMENTATION TO BE FILED IN LIBER 3 OF LAND CORNERS

APR 24 1995 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
COMMISSION

STATE OF MICHIGAN
 ROSCOMMON COUNTY
 RECORDED

For corners in

<u>Roscommon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> , R <u>2W</u>	<u>A-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

14 NOV 94 3:06 P.M.

ROBERT W. SMITH
 REGISTER OF DEEDS
ROSCOMMON COUNTY
PEER GROUP APPROVAL
 DATE 10-20-94
 Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey on September, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | |
|------------------------------------|-----------------------|
| Post set by John Burt 1838 | 1992 LCRC L. Cavanagh |
| Birch 6" S37°W 7 links | Liber 1, Page 311 |
| Tamarak 8" N48°W 8 links | Found axle shaft |
| | New Witt |
| 1982 Section Subdivision by Norman | 3" Cedar N60°E 18.18' |
| Parker R.L.S. | 6" Cedar S57°E 50.17' |
| Calls for axle shaft in pipe | 5" Cedar S85°W 36.66' |
| | 5" Cedar N30°W 16.65' |

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found axle shaft in pipe
 - All 1992 Witnesses

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 1/2" x 24" cast iron Roscommon County Monument inside of 3" P.V.C. Pipe
 17614 - 1994
 nail and tag in 6" Cedar S57°E 50.10'
 nail and tag in 3" Cedar N60°E 18.06'
 nail and tag in 5" Cedar N30°E 16.60'
 nail and tag in 5" Cedar S85°W 36.55'

Is accepted as the best available evidence of the position of the original corner.

Signed by Larry L. Cavanagh Date 11/1
 Surveyor's Michigan License No. 17614

