

SURVEY & REMONUMENTATION

8354

APR 24 1995

ROSCOMMON COUNTY REMONUMENTATION

TO BE FILED IN LIBER 3 OF LAND CORNER

LAND CORNER RECORDATION CERTIFICATE

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> , R <u>2W</u>	<u>B-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

14 NOV 94 3:07 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS
ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 10-20-94

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9	•											
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 Post set by William Burt 1852 B-9
 Spruce 6" N20°W 7 links Set 1/2" x 18" capped bar
 W. Pine 10" S44°E 20 links Wit: 6" W. Pine N38°W 18.1
 5" R. Pine S65°W 31.5
 Schaaf Notes indicate corner found or re-established 5" W. Pine S16°E 10.1
 or replaced 4" Maple N65°E 26.4
 no date

1994 Section Subdivision Section 19, Larry Cavanagh

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No original evidence found
 Found 1/2" x 18" capped iron as set in Liber 1, Page 311. All accessories found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 2 1/2" x 24" cast iron Roscommon County Monument
 17614 - 1994
 N38°W nail and tag in 6" W. Pine 18.1'
 S65°W nail and tag in 5" R. Pine 31.5'
 S16°E nail and tag in 5" W. Pine 10.1'
 N65°E nail and tag in 4" Maple 26.4'

Is a careful and faithful establishment of the position of the corner.

Signed by Larry L. Cavanagh Date _____
 Surveyor's Michigan License No. 17614



Date 10/20/94 Peer Group Approved

LIBER 3 PAGE 135