

**SURVEY &
REMONUMENTATION**

APR 07 1998

SECTION

9252

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in
Roscommon County

16 DEC 97 12:28 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

I. Public Land Survey

Located in:	Corner Code #
T22N R 2W	E-7
T _____	_____
T _____	_____
T _____	_____

FILE IN LIBER 3 OF LAND CORNER

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey October, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

WILLIAM BURT 1852 SET POST ASPEN 10" S42W 30 LKS W. PINE 6" N19E 20 LKS	LCRC L2 P195 1970'S 1 1/4" PIPE 19" R. PINE N35W 25.56' 17" TRI B. OAK S20W 22.58' 13" B. OAK S85E 26.1' 8" W. OAK N30E 42.1'
M SCHAAF 1930'S FD OR ESTABLISHED AND REPLACED CORNER	LARRY CAVANAGH 17614 FD 1 1/4" PIPE WIT: N35°W 25.56' 19" R. PINE S20°W 22.58' 17" TRIPLE B. OAK S85°E 26.10' 13" B. OAK N30°E 42.60' 8" W. OAK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1 1/2" X 36" PIPE WITH CONCRETE BASE
19" R. PINE N35°W 25.56'
17" TRIPLE B. OAK S20°W 22.58'
13" B. OAK S85°E 26.10'
8" W. OAK N30°E 42.60'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY MONUMENT STAMPED 17614, 1997
NAIL & TAG IN 23" R. PINE N60°W 25.93'
NAIL & TAG IN 19" TRIPLE B. OAK S42°W 22.78'
NAIL & TAG IN 14" B. OAK S85°E 26.54'
NAIL & TAG IN 12" W. OAK N48°E 42.86'
CARSONITE POST EAST 1.3'


THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Dec 5, 1997**

Marvin E. Myers
**Marvin E. Myers, P.S.
County Surveyor**

Signed by Larry L. Cavanagh
Surveyor's Michigan License NO. 17614

Date Dec. 11, 1997



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 1975
REVISED JAN., 1983

LIBER 3 PAGE 477