

**SURVEY &  
REMONUMENTATION**

APR 07 1998

**SECTION**

9250

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in  
Roscommon County

16 DEC 97 12:27 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

1. Public Land Survey

Located in:	Corner Code #
T22N R2W	F-7
T_____R_____	_____
T_____R_____	_____
T_____R_____	_____

**FILE IN LIBER 3 OF LAND CORNER**  
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey October, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	35							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

WILLIAM BURT 1852 SET POST W. PINE 8" S75E 44 LKS W. OAK 6 N32W 10 LKS	LARRY L. CAVANAGH 17614 1989 1/2" BAR 3" BALSAM S54W 23' 6" SPRUCE S89E 21.44' 10" SPRUCE N28W 24.0' 3" BALSAM S18E 36.6'
M. SCHAAF 1930'S FD BUT NOT REPLACED CORNER	LARRY L. CAVANAGH 17614 LCRC L1 P290 1989 SET 1/2" X 18" STEEL BAR 3" BALSAM S54W 23.55' 6" SPRUCE S89E 21.05' 10" SPRUCE N28W 24.0' 3" BALSAM S18E 36.6'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 1/2" BAR N63°09'05"W 12.77 FEET FROM SINGLE PROPORTIONATE POSITION, NOT ACCEPTED  
THIS CORNER WAS ESTABLISHED AT SINGLE PROPORTIONATE DISTANCE BETWEEN E-7 (N89°09'09"W 2640.47') AND  
H-7 (S89°09'09"E 5280.93')


**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

SET ROSCOMMON COUNTY MONUMENT STAMPED 17614, 1997  
NAIL & TAG IN 5" BALSAM S42°E 37.55'  
NAIL & TAG IN 10" BALSAM N32°E 39.67'  
NAIL & TAG IN 7" CEDAR S68°W 74.65'  
NAIL & TAG IN 8" BALSAM N20°W 36.68'  
CARSONITE POST NORTH 1.0'

A CAREFUL AND FAITHFUL ESTABLISHMENT OF THE POSITION OF THE CORNER.

**ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE Dec 5, 1997**

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Larry L. Cavanagh* Date Dec. 11, 1997  
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 23, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

LIBER 3 PAGE 475