

# SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

4730

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Roscommon</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>2W</u>	<u>L - 9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

11 JUL 96 11:28 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

**TO BE FILED IN LIBER 3 OF LAND CORNER  
Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on June 18, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO - Aug 1852 W. Burt	L.L. P. 235 T.L. Lapham	Mar 17, 1994 L.L. Cavanagh
Mon - Post	Mon - 1/2" Rerod	Mon - 1/2" Bar in Corner
Wit - 8" Aspen N9 1/2°E 9 Lks	Wit - 18" J. Pine S05°E 30.23	Wit - 6" J. Pine N20°W 100.2
7" S. Pine S24°W 30 Lks	12" J. Pine S45°E 35.28	8" J. Pine N30°E 9.86
	4" Oak N05°E 48.85	12" J. Pine S30°E 23.53
		14" J. Pine S10°E 29.90

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1/2" bar in centerline of E-W road  
Blaze SE face 10" J.Pine N07°W 10.07'  
Found blaze SW face 13" J.Pine N37°E 9.86'  
Found blaze NW face 11" (dead) J.Pine S26°E 23.53'  
Found blaze on face 17" J.Pine S07°E 29.90' (30.31' to nail)  
Found nail West side 8" B.Oak N10°E 45.81'  
Accepted as a reestablishment of the position of the original corner.  
Replace 1/2" bar with standard Roscommon county monument.

**ROSCOMMON COUNTY**

**PEER GROUP APPROVAL**

**DATE** June 17, 1996

*Marvin E. Myers*

**Marvin E. Myers, P.S.  
County Surveyor**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon. - Standard Roscommon County Monument stamped "MEM 31600 L-9"  
WIT: Steel fence post S04°W 20.10'  
Set nail SW side 12" Poplar N36°W 43.55'  
Nail W. side 8" B.Oak N10°E 45.81'  
Nail SW side 11" J.Pine S40°E 35.39'  
Set Carsonite Post North 33.00'

Signed by *Marvin E. Myers*

Date June 24, 1996

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

LIBER 3 PAGE 312