

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Rescommon  
(County) \_\_\_\_\_

Corner Code #

1. Public Land Survey      T 22N R 2W      M-10  
   T 22N R 1W      A-10

2. Property Controlling  
in Section      S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
                                 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Section      S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
                                 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED  
27 SEP 1999 9:16:37 AM  
ROBERT W. SMITH  
REGISTER OF DEEDS

TO BE FILED IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Carl T. Kiiskila, in a field survey on September 9, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO- May 1838 John Brink D.S. set quarter section post  
Wit: 11" Pitch Pine S36.5°W 23 Links  
10" Pitch Pine N41.5°W 75 Links

Larry Cavanagh RLS# 17614, July 28, 1978, Liber 351,  
Page 57, shows corner with no description of monument.  
Wit: Spike in East face of Power Pole S20°E 88.90'  
12" B. Oak Spike in South face S70°E 36.22'  
8" R. Pine N60°E 44.80'  
24" B. Oak Spike in NE face N50°W 87.50'  
1/4" Bar West 33'

G. Henning RLS# 2240 shows corner position midway and on line between corners M-9 and M-11.

Larry Cavanagh RLS# 17614, April 5, 1979, Liber 361,  
Page 459, shows corner with no description of monument.  
Wit: 12" B. Oak Spike in South face S70°E 36.22'  
8" R. Pine N60°E 44.80'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

Found a 1 5/8" automotive valve in the centerline of North-South Road. Accepted 1 5/8" automotive valve as set by G. Henning, and used by Larry Cavanagh as the best available evidence of the original corner position. Replaced 1 5/8" automotive valve with standard Roscommon County monument.

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE Sept 10, 1999

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Roscommon County Monument in pavement box.  
Wit: Set nail in 16" Red Pine N66°E 45.17'  
Set nail in 16" Red Pine S57°E 45.48'  
Set nail in 3" Jack Pine N50°W 37.96'  
Set nail in Power Pole S25°W 88.90'



Signed by: Carl T. Kiiskila  
Surveyor's Michigan License No.: 33981

Date: 9-16-99



SURVEY &  
RECORDATION  
MAR 1 2000  
SECTION