

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Roscommon

(County)

Corner Code #

1. Public Land Survey		T	22N		R	2W		M-11
		T	22N		R	1W		A-11
2. Property Controlling in Section	S	T			R			
	S	T			R			
3. Miscellaneous Property in Section	S	T			R			
	S	T			R			

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on September 9, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO- May 1838 John Brink D.S. set quarter section post
Wit: 16" Yellow Pine S71°W 12 Links
8" White Oak N31°W 27 Links

G. Henning Liber 269, Page 482, November 27, 1972, shows corner. No monument description or witnesses were recorded.

Roscommon County Dept. of Engineering Jan. 27, 1965, engineer N. Sageman found a 1/4" pipe for corner, per 1948 road plans.

G. Henning RLS Liber 333, Page 311, July 12, 1977, shows corner.

Wit: 9" B. Oak N38°E 88.0'
10" B. Oak N83°E 79.7'

G. Henning RLS# 2240, section 25 sketch, no date shows corner position. No monument description or witnesses were recorded.

Larry Cavanagh RLS #17614 Liber 361, Page 459, March 20, 1979, found 1"X24" pipe in corner.

Wit: 9" B. Oak N38°E 88.0'
10" B. Oak N83°E 79.7'


B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

Found 1 5/8" automotive valve in the centerline of North-South Road. Accepted 1 5/8" automotive valve as the best available evidence of the original corner position.
Replaced 1 5/8" automotive valve with standard Roscommon County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Standard Roscommon County Monument in pavement box.

Wit: Set nail in 12" Oak N45°E 87.92'
Set nail in Utility Pole S36°E 39.06'
Set nail in Utility Pole S51°W 39.48'
Center or Crimson Maple N42°W 77.72'



Signed by: Carl T. Kiiskila
Surveyor's Michigan License No.: 33981

Date: 9-16-99