

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Roscommon _____
(County)

		Located In		Corner Code #
1. Public Land Survey	T	<u>22N</u>	R <u>2W</u>	<u>K-11</u>
	T	<u>22N</u>	R <u>2W</u>	<u>L-11</u>
2. Property Controlling in Section	S _____	T _____	R _____	_____
	S _____	T _____	R _____	_____
3. Miscellaneous Property in Section	S _____	T _____	R _____	_____
	S _____	T _____	R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on August 8, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11												●	●
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-11 GLO- William Burt D.S. 1852
Set post, corner of sections 25, 26, 35, and 36.
Wit: White Pine 15 N42.5°E 45 Links
White Pine 30 S31°W 98 Links
George Henning RLS 2240 set a 1/2" bar for corner c. 1970 while doing a survey in section 25.
No witnesses recorded.

L-11 GLO- William Burt D.S. 1852
Set quarter section post
Wit: Yellow Pine 12 N60°W 25 Links
Yellow Pine 14 S60°E 10 Links

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

K-11 Found and accepted a 1/2" iron rod as set by G. Henning RLS #2240

L-11 Reestablished the south quarter corner of section 25 by single proportionate measurement midway and on line between found corners to the East and West. This position fits closely to G. Henning mathematical position for this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11 Replaced 1/2" Iron rod with standard DNR Monument
Wit: 12" Maple S46°W 38.91'
16" Red Pine N55°W 18.44'
*12" Jack Pine S40°E 11.56'
3" Maple N05°E 31.58'
Carsonite Post North 1'
* Old witnesses by others

L-11 Set Standard DNR monument
Wit: 3" Oak N24°W 12.58'
3" Oak S60°W 15.60'
5" Oak S07°E 15.49'
4" Oak N65°E 21.72'
Carsonite Post North 1"

Signed by: _____

Carl T. Kiiskila

Date: _____

9-8-99

Surveyor's Michigan License No.: _____

33981

