

9163

ROSCOMMON COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

MAY 28 1997

COMMISSION

For corners in

<u>ROSCOMMON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 22 NR 4W	M - 11
	T 22 NR 3W	A-11
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

6 DEC 96 4:25 P.M.

ROBERT W. SKITH
REGISTER OF DEEDS

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, TIMOTHY L. LAPHAM, in a field survey on July, 9, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M - 11 GLO, BRINK 1836, SET POST, 12" WHITE PINE S31W 30 LNKS, 12" YELLOW PINE N24W 26 LNKS; LCRC, UNKNOWN (REC 2-276), 1/2" BAR, 3 WITS; PLAT OF HIGHLAND ACRES, OSTLING (REC 6-75, 12/30/1970), NO MONUMENT MATERIAL OR WITS; SURVEY, CAVANAGH (REC 437-474-6, 2/09/1983), NO MONUMENT MATERIAL OR WITS;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 11 NO EVIDENCE OF GLO FOUND. FOUND 1/2" BAR IN ACCORD WITH RECORDED LCRC. DISTANCE SOUTH MATCHES PLAT OF HIGHLAND ACRES. ACCEPTED FOUND MONUMENT AS BEST EVIDENCE OF POSITION OF ORIGINAL CORNER. SEE DOSSIER FOR ADDITIONAL INFORMATION.

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Dec 16th 1996

Marvin E. Myers
Marvin E. Myers, P.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 11 SET 2" X 21" CAST IRON MONUMENT WITH BRASS ROSCOMMON COUNTY PLATE IN MONUMENT BOX.
N46E 108.41' 12" OAK, NAIL IN SOUTH SIDE OF TREE
S24E 61.51' 10" OAK, NAIL IN EAST SIDE OF TREE
S46W 41.84' GUIDE POLE, NAIL IN WEST SIDE OF POLE
N42W 41.04' UTILITY POLE, NAIL IN EAST SIDE OF POLE

Signed by *Timothy L. Lapham*
Surveyor's Michigan License No. 27595

Date 10/01/1996

