

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

28 APR 99 11:53 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T22N R3W C-11
T R
T R
T R

I, Larry L. Cavanagh, in a field survey April, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

- WILLIAM BURT 1849 SET POST S PINE 14 N36°E 40 S PINE 22 S60°W 50
JIM RICHARDSON, RLS 1937 FD PIPE AT CORNER ONE B - ONE NBT NBT- B. OAK 12 N52 1/2°W 71.75' S PINE 7 N51 1/2°E 74.0' W OAK 6 S29 1/2°E 19.4'
GEORGE D. HENNING RLS 1958 1 1/4" PIPE IN CORNER (OLD) 5" W OAK S68°W 69.8' 5" B OAK S9°E 70.8' 12" J PINE N48°E 74.4' 14" W OAK N53°W 71.6'
OSTLING SURVEY'S INC 1970 FD 1 1/4" PIPE SAME WITNESSES AS ABOVE
LCRC L2, P245 1970'S N45°W 56.88' 24" POPLAR S30°E 19.33' W OAK (TAG) S50°W 31.30' P.P. 12" OAK N30°W 71.3'
LARRY L. CAVANAGH RLS 1982 SAME WITNESSES AS 1976 SURVEY
LARRY L. CAVANAGH RLS 1982 SAME WITNESSES AS ABOVE
1971 (ROSCOMMON COUNTY RD PLANS) 1 1/2" PIPE 31.28' WEST OF PI #4 24" POPLAR N45°W 56.88' P.P. S50°W 31.30' 14" W OAK S30°E 19.33'
C. EUGENE OSTLING RLS 1975 SAME WITNESSES AS 1970 SURVEY
LARRY L. CAVANAGH RLS 1976 FD 1 1/2" PIPE 12" W OAK S20°E 19.33' (TAG) 12" OAK N30°W 71.3' TELE POLE S45°W 31.2'
LARRY L. CAVANAGH RLS 1980 LCRC L1, P233 FD 1 1/2" PIPE 24" POPLAR N45°W 56.88' 14" W OAK S30°E 19.33' P.P. S 50°W 31.30' 12" OAK N30°W 71.3'

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column C and row 11.

LARRY L. CAVANAGH RLS 1988 SAME WITNESSES AS ABOVE

LARRY L. CAVANAGH RLS 1990 SAME WITNESSES AS ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/4" X 18" PIPE 17" W OAK S20°E A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614 1999 WIT: NAIL & TAG IN 17" W OAK S20°E 19.10' NAIL & TAG IN 14" W PINE N34°W 66.56' NAIL & TAG IN P.P. N15°E 55.13' NAIL & TAG IN P.P. S53°W 42.66' CARSONITE POST S15°E 20.95'

ROSCOMMON COUNTY PEER GROUP APPROVAL DATE April 19, 1999

Marvin E. Myers, P.S. County Surveyor



Signed by Larry L. Cavanagh Date April 23, 1999 Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983