

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED  
28 APR 99 11:53 A.M.

For corners in  
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T22N R 3W C-12  
T R  
T R  
T R

ROBERT W. SMITH  
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

WILLIAM BURT 1849  
SET POST  
HEMLOCK 9 S15°E 26  
W. PINE 18 N15°E 19

C. EUGENE OSTLING, RLS 1975  
FD 1/2" BAR  
NO WITNESSES

JIM RICHARDSON, RLS 1937  
RE-ESTABLISHED COR-BAR  
NBT- DEAD B OAK 6 N6 1/2°W 73.05'  
DEAD B OAK 5 N41°E 37.0'  
Y PINE S (STUMP) 10 S57 1/4°E 53.1'

LARRY L. CAVANAGH, RLS 1988  
NO MONUMENT MATERIAL CALLED OUT  
NAIL IN 14" POPLAR N80°E 18.3'  
NAIL IN 12" POPLAR S52°E 18.6'  
NAIL IN 10" CHERRY S30°W 19.3'  
4" POPLAR N70°W 28.1'

OSTLING SURVEYS INC. 1970  
FOUND 1/2" BAR  
NO WITNESSES

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	18	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 24" BAR  
SPIKE IN 10" CHERRY S30°W 19.3' (TREE DEAD)  
SPIKE IN NORTH SIDE OF 14" POPLAR N80°E 18.3'  
FOUND 12" POPLAR STUMP S52°E 18.6'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614 1999  
WIT: SPIKE IN NORTH SIDE OF 14" POPLAR N80°E 18.3' (OLD)  
NAIL & TAG IN 7" POPLAR S50°W 17.33'  
NAIL & TAG IN 12" B OAK N55°W 42.51'  
NAIL & TAG IN 16" NORWAY S44°E 61.86'  
CARSONITE POST WEST 4.05'

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE APRIL 19, 1999

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Larry L. Cavanagh* Date April 23, 1999  
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983