

3893

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Roscommon County

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

19 MAY 98 11:08 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

I. Public Land Survey

Located in:	Corner Code #
T22N R 3W	C-13 ✓
T21N R 3W	C-1
T _____ R _____	_____
T _____ R _____	_____

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

FILE IN LIBER 3 OF LAND CORNE
Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1838
SET POST COR.
BLACK ASH 14 N22E 47
BLACK ASH 14 N39 1/2W 37

LCRC 1970'S
LIBER 2 PAGE 246
2" PIPE IN CONC. BLOCK
S3°E 34.65' 16" MAPLE
N3°E 16.70 6" POPLAR

DNR 1930'S
FD U. S. BEARINGS
NET W. PINE 8 N57E 30.5
TAM 7 N75 1/2W 19

SCHAAF INDICATES IRON
SET

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2" X 34" PIPE IN CONCRETE
1" X 18" PINCH PIPE SOUTH EDGE OF 2" PIPE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614 (IN PLACE OF 2" X34" PIPE IN CONCRETE)
WT: NAIL & TAG IN 6" BALSAM N38°E 9.93'
NAIL & TAG IN 5" ASH N67°W 22.85'
NAIL & TAG IN 9" ASH S38°W 58.69'
CENTERLINE OF ROAD IS SOUTH 15.0'
CARSONITE POST NORTH 2.0'

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

SURVEY &
REMONUMENTATION

OCT 05 1998

SECTION

ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE MAY 16 1998
Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh*
Surveyor's Michigan License NO. 17614

Date May 16, 1998

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 504