

3695

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in
Roscommon County

28 APR 99 11:53 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

	Located in:	Corner Code #
1. Public Land Survey	T22N R 3W	D-11
	T N R W	
	T R	
	T R	

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

WILLIAM BURT 1849
SET POST
Y PINE 18 S70°W 41
W PINE 26 N20°E 39

GEORGE D HENNING RLS 1958
1/2" X 3/8" IRON BAR IN 1/4 COR
4" CONC. MONUMENT 33' NORTH
8" B. OAK N31°E 57.5'
8" B OAK S35°E 60.5'
6" W. OAK S46°W 55.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 2" STEEL BAR IN CORNER
FOUND 1/2" X 3/8" STEEL BAR S68°W 3.3' FROM 1/4 POST (REMOVED)
FOUND 4" CONCRETE MONUMENT 33.92' NORTH
FOUND 6" W. OAK, NOW 11" S46°W 55.6 MEN

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614 1999
WT: NAIL & TAG IN 11" W. OAK S46°W 55.74' (OLD)
NAIL & TAG IN 12" W. OAK S20°E 20.94'
NAIL & TAG IN 30" R. OAK N34°W 37.12'
NAIL & TAG IN 17" W. OAK N25°E 34.66'
4" CONCRETE MONUMENT NORTH 33.92'
CARSONITE POST SOUTH 13.35'

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE APRIL 19, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by Larry L. Cavanagh Date April 23, 1999
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 584