

8952 FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF ROSCOMMON

DEC 16 9 21 AM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N R 3W	E-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Robert L. ...*  
REGISTER

**ROSCOMMON COUNTY  
PEER GROUP APPROVAL**  
DATE 11-30-93  
TO BE FILED IN LIBER 3 OF LAND CORNE  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Larry L. Cavanagh, in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970; the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

W/post placed by Wm A. Burt 1849	1972 L. Cavanagh Sec survey Sec 16	1979 Deerwood Village L-7,P-31
Aspen 6" N78°E 12	Boat spike in MSHD Pav't Box	1957 MDOJ plans apparent same location,
Aspen 9" S30°W 18	Street sign S40°W 48.1	Also older plan (Undated)
1940-present Numerous surveys	Power Pole S40°E 38.4	
1940 Houghton Beach Sub. L-2,P-33	1977 L. Cavanagh land survey	
1946 Robert T. Ostling sec survey	Boat spike in MSHD Pav't Box	
1/2"x18" bar	Street sign S40°W 48.1	
Spike in Aspen 12" S45°E 69.8	Power pole S40°E 38.4	
Spike in Aspen 12" S29 1/2°W 75.3	Spike in W side of P.P. N10°E 31.4	
	No parking sign post N50°W 49.45	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Boat spike in Monument Box 1.5' North of centerline of M-55, and is accepted as the best evidence of the position of the original corner.

See filed dossier for detail of report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon Co. Std. Mon in Pav't Box E. edge pav't Box stamped E-6 17614  
 S59°W Nail & tag in P. pole 58.08  
 N2°E Nail & tag in P. pole 40.64  
 S64°E Nail & tag in Htn Lk Hist. Vill. Sign post 102.45  
 N22°E Nail & tag in 6" Maple 78.90



Signed by Larry L. Cavanagh Date 12-15-93  
Surveyor's Michigan License No. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

Date November 30, 1993 Peer Group Approved