

3907

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey T22N R3W E-9
T R
T R
T R

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

19 MAY 98 11:11 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-12. A dot is present in cell F9.

A. Description of original monument and accessories and/or subsequent restoration

WILLIAM A. BURT 1849 LCRC, 1970'S L2, P236
SET POST CORNER IRON BAR
Y. PINE 16 S37W 22 24' OAK S18W 68.89
Y. PINE 15 N80E 28 12' OAK N41W 56.98
LARRY L. CAVANAGH, 17614 1978
DNR 1930'S SAME WITNESSES
FOUND U.S. BEARINGS
NO TREES
LARRY L. CAVANAGH, 17614, 1993
RESET 1/2" BAR IN COR FROM WIT.
G.D. HENNING RLS 1942 SP IN 20' B. OAK N17°E 68.45'
1/2" IRON BENT IN LOOP SURROUNDED SP IN 12' NORWAY S63°W 71.75'
BY STONE IN CENTER OF RD INTSEC. SP IN 12' R. OAK S43°E 57.40'
B. OAK 20' BEARS N17 1/2E 68.3 SP IN 10' W. PINE N53°W 75.90'
MKD NBT (OLD)
N. PINE 12' BEARS S63 1/2W 71.5 LARRY L. CAVANAGH 17614 1993
MKD NBT (OLD) FD 1/2" IR.
R. OAK 12' BEARS S43 1/2E MKD SAME WIT. AS ABOVE
NBT (OLD)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 18" STEEL BAR OVER A PILE OF ROCKS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614I
WIT: NAIL & TAG IN 27" B. OAK N20°E 68.21'
NAIL & TAG IN 13" W. PINE N50°W 76.32'
NAIL & TAG IN 15" NORWAY S64°W 72.01'
NAIL & TAG IN 17" R. OAK S41°E 57.45'
CARSONITE POST S51°E 41.46'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

SURVEY &
REMONUMENTATION

OCT 05 1998

SECTION

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE MAY 15 1998

Marvin E. Myers, P.S.
County Surveyor



Signed by [Signature] Date MAY 16, 1998
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983