

3690

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in  
Roscommon County

28 APR 99 11:52 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

	Located in:	Corner Code #
1. Public Land Survey	T22N R 3W	E-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____

FILE IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

WILLIAM BURT 1849  
SET POST  
W. PINE 20 N35°E 30  
W. PINE 15 S20°W 32

GEORGE D. HENNING RLS 1958  
1/2" X 36 IRON BAR IN 1/4 COR  
4" CONC MONUMENT 33' WEST  
(CALLED FOR IN HENNING SURVEY)  
5" MAPLE N57°W 53.6'  
7" MAPLE N76°E 38.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" X 30" PIPE  
8" MAPLE N76E 38.5'  
4" MONUMENT 33' WEST

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614 1999  
WIT: NAIL & TAG IN 8" MAPLE N76°E 38.64'  
NAIL & TAG IN 6" W OAK N15°E 24.50'  
NAIL & TAG IN 5" W PINE S3°E 16.95'  
NAIL & TAG IN 6" MAPLE N48°W 53.29'  
NAIL & TAG IN 4" MONUMENT WEST 33.0'  
CARSONITE POST EAST 1.0'



ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE April 19, 1999

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

Signed by Larry L. Cavanagh Date April 23, 1999  
Surveyor's Michigan License NO. 17614