

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in
Roscommon County

28 APR 99 11:53 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

1. Public Land Survey

Located in:	Corner Code #
T22N R3W	E-11
T R	
T R	
T R	

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	18		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- WILLIAM BURT 1849
SET POST
Y PINE 16 N67°W 8
Y PINE 18 N26°E 43
- GEORGE D HENNING, HLS 1958
1/2" X 3/8" BAR IN SEC COR
4" CONC MON 33 NORTH
6" B. OAK N19°E 55.8'
8" B. OAK S55°E 53.4'
10" B. OAK S46°W 49.8'
- OSTLING SURVEYS INC., 1970
FD 1/2" STEEL BAR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- NO MONUMENT FOUND IN CORNER
- FOUND 4" CONCRETE PLAT MONUMENT 33.0' NORTH
- FOUND 6" B. OAK S55°E (NOW 8") *53.4' N.E. 84*
- FOUND 1 1/2" PIPE NOT IDENTIFIED AS SCHAAF S85°E 23.39' (REMOVED)
- F-11 2619.68, GLO 2612.9
- D-11 2626.09, GLO 2616.9
- CORNER RE-ESTABLISHED FROM CONCRETE MONUMENT AND OAK WITNESS (SE)
- THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614 1999
- WIT: 4" CONC. MON N1°21'W 33.0'
- NAIL & TAG IN 6" CHERRY S176°W 15.06'
- NAIL & TAG IN 8" B. OAK S55°E 53.30'
- NAIL & TAG IN 16" B. OAK N57°W 31.82'
- NAIL & TAG IN 23" B. OAK N43°E 21.26'
- CARSONITE POST NORTH 13.7'

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE *April 19, 1999*

Marvin E. Myers, P.S.
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh* Date *April 23, 1999*
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983