

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in
Roscommon County

28 APR 99 11:53 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

Located in: Corner Code #

1. Public Land Survey

T22N	R3W	E-12
T	R	
T	R	
T	R	

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

WILLIAM BURT 1849 SET POST W OAK 11 N82°E 6 R. OAK 5 S46°W 15	C EUGENE OSTLING RLS 1975 L305, P687
C EUGENE OSTLING, RLS 1970 SET 1/2" IRON NO WITNESSES	LARRY L. CAVANAGH RLS 1978 1/2" BAR 4" W PINE WEST 2.65' 10" OAK N45°E 15.83' 10" OAK S45°W 16.7' 8" OAK EAST 5.29'
LCRC L2, P249 1970'S 1/2" BAR 12" W OAK S82°E 4.3 4" W PINE S78°W 2.9' 12" W OAK N50°E 14.4'	LARRY L. CAVANAGH RLS 1979 LCRC L1, P114 1/2" BAR SAME WITNESSES AS ABOVE
C EUGENE OSTLING RLS 1974 1/2" BAR SAME WITNESSES AS ABOVE	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON BAR
NO WITNESSES FOUND
THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614 1999
WIT: NAIL & TAG IN 6" W OAK N82°E 38.55"
NAIL & TAG IN 10" W OAK S50°E 47.51"
NAIL & TAG IN 3" ASPEN N30°W 33.23'
NAIL & TAG IN 4" CHERRY S53°W 18.21'
CARSONITE POST WEST 1.0'

ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE April 19, 1999
Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh* Date April 23, 1999
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983