

FEB 18 1994  
**8954**  
 COMMISSION

**ROSCOMMON COUNTY REMONUMENTATION**

STATE OF MICHIGAN  
 COUNTY OF ROSCOMMON

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

Dec 16 9 21 AM '93

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>3W</u>	<u>F-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Robert...*  
 REGISTERED

**ROSCOMMON COUNTY  
 PEER GROUP APPROVAL**

DATE 12-14-93

TO BE FILED IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- |                                  |                                   |
|----------------------------------|-----------------------------------|
| W/post placed by Wm A. Burt 1849 | 1979 Seneca Village L-7,P35       |
| Pine 6" S50°E 30                 | 1989 Seneca Village No. 2 L-7,P63 |
| Tamarack 8" N38°W 31             | 1992 L. Cavanagh land survey      |
| 1975± Liber 2 corner record      | 3/4" pipe                         |
| 1/4 cor 3/4" pipe                | 7" Cedar N66°W 33.4               |
| 7" Cedar N66°W 33.4              | 8" Cedar S20°E 28.25              |
| 8" Cedar S20°E 28.25             | 8" Cedar S55°E 37.75              |
| 8" Cedar S55°E 37.75             |                                   |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found no original evidence  
 Found 3/4" pipe  
 All 1975-1992 witnesses  
 8" Cedar recorded as S55°E 37.75 was found to be N55°E 37.73 accepted as the best available evidence of the position of the original corner.

See filed dossier for detail of report.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Set Roscommon Co. Std. Mon stamped F-S 17614
- N66°W Nail & tag in 7" Cedar 33.65
- S20°E Nail & tag in 8" Cedar 28.45
- N55°E Nail & tag in 8" Cedar 38.20
- South Nail & tag in 8" Ash 6.61
- Carsonite post at North edge of Monument



Signed by Larry L. Cavanagh  
 Surveyor's Michigan License No. 17614

Date 12-15-93

Date December 14, 1993 Peer Group Approved