

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

8955

FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Dec 16 9 21 AM '93

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N, R 3W	F-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

[Signature]
REGISTER

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 11-30-93

TO BE FILED IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- W/Post placed by Wm A. Burt 1949
- Y. Pine 18" S48°E 26
- W. Pine 18" N25°W 20
- 1972 L. Cavanagh Sec survey S½ Sec 16
- 16" W. Oak S80°E 23.1
- 13" Norway N30°E 9.4
- 1973 Land corner recordation
- Found solid capped iron
- 14" Oak S80°E 23.40
- 10" Pine N30°E 9.43
- Nail NE Face 10" double Oak N35°W 49.85
- Nail E Face 12" Poplar N40°W 54.35
- Nail S Face 18" Oak S35°E 73.75
- 1975± Liber 2 corner record
- 1/2" bar
- 16" W. Oak S80°E 29.1
- 13" Norway N30°E 9.4
- 1977 L. Cavanagh land survey
- Fd 1/2" bar
- 9" W. Oak N65°E 80.0
- 9" R. Oak S35°E 57.46
- 3" W. Oak S30°W 39.1
- 1/2" bar N0°18'03"E 33.0
- 1992 Gosling Czubak Land Survey
- Found boat spike
- N13°E 24.01 J. Pine 10"/fd Nail
- N10°E 46.77 Oak 12"/fd Nail
- S51°W 48.40 Oak 16"/fd Nail
- S40°E 49.00 R. Pine 10"/Spk

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod with all Liber 1, page 87 Witnesses EXCEPT SE witness, NW witness now stump, and is accepted as the best available evidence of the position of the original corner.

See filed dossier for detail of report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Roscommon Co. Std Mon stamped F-7 17614
- N20°W Nail & tag in 6" Maple 49.57
- N56°E Nail & tag in 18" R. Oak 77.52
- N39°E Nail & tag in 12" B. Oak 57.74
- S35°W Nail & tag in 15" poplar 54.28 (Previous)



Signed by *Larry L. Cavanagh* Date 12-15-93
Surveyor's Michigan License No. 17614

Date November 30, 1993 Peer Group Approved
LIBER 3 PAGE 21