

3908

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

19 MAY 98 11:11 A.M.

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T22N R3W F-9
T R
T R
T R

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	25	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration

WILLIAM A. BURT 1849
SET POST CORNER
Y. PINE 16 S52W 30
Y. PINE 12 N34E 33

LARRY L. CAVANAGH, SURVEY 1993
FD DNR MON
9' J. PINE N24°E 45.85'/SP
5' W. PINE N10°W 42.24'/SP
18' B. OAK S64°W 38.40'/SP
12' N. PINE S62°E 39.76'/SP
BOAT SPIKE NORTH 16.12'

DNR 1930'S
FOUND STUMP OF U.S.
BEAR TREE N.B.T.
SPRUCE PINE 10 S40°E 45 1/2
SPRUCE PINE 9 N72°E 50

GOSLING CZUBAK ASSOC. 1992
FD BOAT SPIKE
N13°E 24.01' J. PINE 10'/FD NAIL
S10°W 46.77' OAK 12'/FD NAIL
S51°W 48.40' OAK 16'/FD NAIL
S40°E 49.0' R. PINE 10'/SPK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND DNR MONUMENT STAMPED ILS 30083
FOUND BOAT SPIKE NORTH 16.12'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

LEFT DNR MONUMENT IN PLACE
WIT: BOAT SPIKE ON CENTERLINE NORTH 16.12'
NAIL & TAG IN 9' J. PINE N24°E 45.85'
NAIL & TAG IN 5' W. PINE N10°W 42.24'
NAIL & TAG IN 18' B. OAK S64°W 38.40'
NAIL & TAG IN 12' NORWAY PINE S62E 39.76'
LOT CORNER NORTH 49.08'
CARSONITE POST SOUTH 20.4'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

SURVEY &
REMONUMENTATION

OCT 05 1998

SECTION

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE MAY 15 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh* Date May 16, 1998
Surveyor's Michigan License No. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 519