

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

28 APR 99 11:53 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

For corners in  
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T22N R3W F-11  
T R  
T R  
T R

FILE IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

WILLIAM BURT 1849  
SET POST  
S PINE 6 N55°E 11  
S PINE 4 S12°W 12

C. EUGENE OSTLING, RLS  
1970 SURVEY  
SET 1/2" STEEL BAR

LARRY L. CAVANAGH, PS 17614 1995  
3" MAPLE N57°W 28.79'  
4" OAK N31°E 15.85'  
10" OAK S29°E 15.98'  
16" OAK S48°W 19.06'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 18" BAR AND ALL WITNESSES  
#40 SPIKE IN ALL WITNESSES

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614  
WIT: #40 SPIKE IN 3" MAPLE N57°W 28.79'  
#40 SPIKE IN 4" OAK N31°E 15.85'  
#40 SPIKE IN 10" OAK S29°E 15.98'  
#40 SPIKE IN 16" OAK S48°W 19.06'  
CARSONITE POST NORTH

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE April 19, 1999

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Larry L. Cavanagh* Date April 23, 1999  
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983