

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF ROSCOMMON  
REGISTERED

8958 FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 16 9 21 AM '93

For corners in **COMMISSION**

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N, R 3W	G-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Richard J. Cavanagh*  
REGISTERED

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 11-30-93

TO BE FILED IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Larry L. Cavanagh, in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

W/post placed by Wm A. Burt 1849 Cedar 10" N39°E 14 Lks B. Ash 9" S39°W 6 Lks 1968 White Deer No. 2 L-6, P-18 1972 L. Cavanagh Sec survey S½ Sec 16 Found pipe 6" B. Ash S80°W 25.0 6" Tw Maple N40°W 28.7	1973 Land corner recordation Fd 3/4" pipe Nail 4" Cedar SE 40.44 Nail 12" Maple NW 40.50 Nail 8" Oak N 55.21 1975± Liber 2 corner record 3/4" pipe 6" B. Ash S80°W 25.0 6" Tw Maple N40°W 28.7	1992 Gosling Czubak Land survey Set 1/2"x18" capped I.R. North 33.00 Fd 17614 Capped I.R. N40°E 55.10 Ash 18"/Fd Spk N20°W 47.81 Maple 10"/Fd Spk N17°W 43.39 Ash 6"/Spk
---	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Iron rod with Gosling Czubak witness (Survey 1992), Also 8" Oak from Liber 1, page 87, and is accepted as the best available evidence of the position of the original corner.  
  
See filed dossier for detail of report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon Co. Std. Mon stamped G-7 17614  
S10°W Nail & tag in 6" Ash 43.31 (Previous)  
N48°W Nail & tag in 14" R. Oak 51.13  
N06°E Nail & tag in 10" B. Oak 55.63 (Previous)  
N35°E Nail & tag in 18" Ash 55.06 (Previous)



Signed by *Larry L. Cavanagh* Date 12-15-93  
Surveyor's Michigan License No. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

Date November 30, 1993 Peer Group Approved  
LIBER 3 PAGE 24