

3909

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey T22N R3W G-9
T R
T R
T R

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

19 MAY 98 11:11 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNER
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration

WILLIAM A. BURT 1849
SET POST CORNER
TAMARACK 6 N45E 10
TAMARACK 7 S55W 5

GEORGE D. HENNING RLS, 1962
WOOD POST SOUTH SIDE TRAIL
SAME WITNESSES AS ABOVE

DNR 1930'S
FOUND U.S. CORNER
NO TREE NEAR

LARRY L. CAVANAGH, 17614 1993
SET 1/2" X 18" BAR FROM 1942 WIT.
S48 1/2"W 35.6' SPRUCE 5' (NOW 10")
N19"W 38.6' CEDAR 5' (NOW 8")
N35"E 47.9' CEDAR 5' (NOW 8")
N75"E 50.8' SPRUCE 5'

GEORGE D. HENNING, RLS, 1942
WOOD POST IN CORNER ON
SOUTH SIDE OF TRAIL ROAD
SPRUCE 5" S48 1/2" 35.68 B.T.
CEDAR 5" N19"W 38.6' B.T.
CEDAR 6" N35"E 47.9' B.T.

Grid table with columns A-M and rows 1-12. A dot is marked at the intersection of column G and row 9.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" BAR (DISTURBED AND OUT OF POSITION)
10" SPRUCE SW
8" CEDAR NW
8" CEDAR NE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614 FROM WITNESS (1942)
WIT: NAIL & TAG IN 10" SPRUCE S48 1/2"W 35.6'
NAIL & TAG IN 8" CEDAR N19"W 38.6'
NAIL & TAG IN 8" CEDAR N35"E 47.90'
NAIL & TAG IN 5" SPRUCE N75"E 50.80'
NAIL & TAG IN 6" CEDAR N20"E 42.42'
CARSONITE POST SOUTH 7.09'

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

SURVEY &
REMONUMENTATION

OCT 05 1998

SECTION

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 140715041998

Marvin E. Myers, P.S.
County Surveyor



Signed by Larry L. Cavanagh Date May 16, 1998
Surveyor's Michigan License No. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 520