

3691

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

28 APR 99 11:52 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T22N	R 3W	G-10
T	R	
T	R	
T	R	

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

WILLIAM BURT 1849
SET POST
W PINE 30 S38°W 14
Y PINE 24 N42°W 23

LARRY L. CAVANAGH PS 1994
SAME WITNESSES AS ABOVE

GEORGE D. HENNING, RLS 1962
30' W PINE STP S28°W 12.0' (ORIG)
24' Y PINE STP N42°W 15.1' (ORIG)
7' J PINE N12°W 12.7' (BLAZE)
8' J PINE N72°E 12.6' (BLAZE)

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIPE WITH DNR 3" ALUMINUM CAP
30' W PINE STP S28°W 12.0'
24' Y PINE N42°W 15.1'
7' JACK PINE N12°W 12.7' (BLAZE)
8' J PINE N72°E 12.6' (BLAZE) NOT STUMP

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

LEFT DNR MONUMENT IN PLACE
WT: BLAZED 10' J PINE N12°W 12.7' (OLD)
30' W PINE STUMP S28°W 12.0' (OLD)
24' Y. PINE N42°W 15.1' (OLD)
NAIL & TAG IN 5' W PINE NORTH 6.64'
NAIL & TAG IN 4' W PINE N68°E 4.98'
NAIL & TAG IN 5' W PINE S55°E 8.0'
NAIL & TAG IN 13' CHERRY S70°W 11.04'
CARSONITE POST SOUTH 0.88'



ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE April 19, 1999
Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by Larry L. Cavanagh Date April 23, 1999
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983