

3910

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T22N R3W H-9

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

19 MAY 98 11:11 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

FILE IN LIBER 3 OF LAND CORNER
Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration

WILLIAM A. BURT 1849
SET POST CORNER
Y. PINE 16 S8W 16
Y. PINE 16 N65E 17

LARRY L. CAVANAGH 17614, 1977
SAME WITNESSES AS ABOVE

DNR 1930'S
FOUND U.S. BEARINGS
NO TREES

LARRY L. CAVANAGH, 17614, 1982
SAME WITNESSES AS ABOVE

GEORGE D. HENNING RLS 1942
ESTABLISHED AT MIDPOINT ON LINE
1' X 24' PIPE IN CORNER WITH POST
E. OAK 16° S3°E 49.5' B.T.
W. OAK 14° N18 1/2°E 44.8' B.T.

LARRY L. CAVANAGH, 17614, 1994
6' MAPLE S86°W 20.30'
15' W. OAK N22°W 56.55'
18' W. OAK N22°E 45.45'
5' NORWAY S60°E 28.32'

GEORGE D. HENNING, RLS, 1962
2" PIPE
16° E. OAK S3°E 49.5' 1942
14° W. OAK N 18 1/2°E 44.8' 1942

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIPE INSIDE 1 1/2" PIPE
15' W. OAK N22°W 56.55'
18' W. OAK N22°E 45.45'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614
WIT: NAIL & TAG IN 15' W. OAK N22°W 56.55'
NAIL & TAG IN 18' W. OAK N22°E 45.45'
NAIL & TAG IN 9' MAPLE S30°W 56.23'
NAIL & TAG IN 4' W. PINE S37°E 56.30'
CARSONITE POST NORTH 33.57'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

SURVEY &
REMONUMENTATION

OCT 05 1998

SECTION

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE MAY 15TH 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh* Date MAY 16, 1998
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983