

SURVEY &
REMONUMENTATION

OCT 05 1998

3911

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

19 MAY 98 11:12 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T22N R3W L-9
T R
T R
T R

FILE IN LIBER 3 OF LAND CORNER
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration

WILLIAM A. BURT 1849
SET POST CORNER
S. PINE 9 N55E 16
S. PINE 7 S55E 15

*GEORGE D. HENNING RLS 1962
IRON IN CENTERLINE OF PAVT
B. OAK 20' N43°E 24.6'
N. PINE 16' N33°W 51.2'
N. PINE 18' S 50 1/2W 39.7'
W. PINE 20' S60°E 22.3'
(1942)

DNR 1930'S
FOUND U.S. BEARINGS
U.S. B.T. W. PINE 20' N17W 25

LCRC L2,P238 1970'S
S30°E 71.5' NORWAY
N68°W 42.1' J. PINE
N68°E 47.4' J. PINE

GEORGE D. HENNING RLS 1942
AS FD IN CENTER OF PAVT
AND E-W RD, IRON IN PAVT
N PINE S29 1/2E 71.6' B.T.
J. PINE S37 1/2W 42.1' B.T.
J. PINE N37 1/2E 47.4' B.T.

LARRY L. CAVANAGH 17614, 1977 SURVEY
IRON IN CENTERLINE OF PAVT
SAME WITNESSES AS 1962 SURVEY

GEORGE D. HENNING RLS 1959
NORWAY S29 1/2E 71.4'
J. PINE S37 1/2W 42.1'
J. PINE N37 1/2E, 47.4'

LARRY L. CAVANAGH, LCRC 1979
3/4" IRON IN PAVT BOX
NORWAY S30°E 71.5'
J. PINE N38°W 42.1'
J. PINE S58°E 47.4'
P.K. IN NE FACE 12" J. PINE
N62°E 48.15

*LARRY L. CAVANAGH 17614, 1996 SURVEY
IRON IN PAVT BOX
B. OAK 20' N43°E 24.60'
N. PINE 16' N33°W 51.20'
N. PINE 18' S50°30'W 39.70'
W. PINE 20' S60°E 22.30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 9" RAILROAD SPIKE IN MON BOX
J. PINE STUMP NW
N. PINE SE
*1962 AND 1996 WITNESSES APPARENTLY MIS-RECORDED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614
WIT: NAIL & TAG IN 18" B. OAK N43°W 69.57'
NAIL & TAG IN 7" NORWAY S41°W 56.65'
NAIL & TAG IN 20" NORWAY S29°E 72.36'
NAIL & TAG IN 10" J. PINE N56°E 61.62'
CARSONITE POST S53°E 58.44'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE MAY 15 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by *Larry L. Cavanagh*
Surveyor's Michigan License NO. 17614

Date MAY 16, 1998



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 522