

3692

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey T22N R 3W I-10
T R
T R
T R

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

28 APR 99 11:52 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Cell (10, I) contains a black dot.

A. Description of original monument and accessories and/or subsequent restoration:

- WILLIAM BURT 1849 SET POST S PINE 7 N44°W 8 S PINE 4 S63°E 2
LARRY L CAVANAGH RLS 1977 L331,P457 SAME WITNESSES AS ABOVE
LARRY L CAVANAGH RLS 1979 SAME WITNESSES AS ABOVE
LARRY L CAVANAGH RLS 1991 (RECORDED IN L2, P277)
LARRY L CAVANAGH PS 1996 SAME WITNESSES AS L2, P241
LARRY L CAVANAGH PS 1998 LCRC L2, P277
LCRC L2, P241 1970'S S80°E 31.4' 12" B OAK S67°W 34.1' 16" B OAK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND 4" CONCRETE MONUMENT NO OLD WITNESSES
THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- LEFT 4" CONCRETE MONUMENT WITH REROD CAP (17614)
WIT: NAIL & TAG IN 12" W OAK S42°E 23.96'
NAIL & TAG IN 11" W OAK N50°W 4.65'
NAIL & TAG IN 6" W PINE N60°E 19.40'
NAIL & TAG IN 15" W OAK N15°W 18.46'
CARSONITE POST NORTH 2.0'

ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE April 19, 1999
Marvin E. Myers, P.S.
County Surveyor



Signed by [Signature] Date April 23, 1999
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 581