

**SURVEY &  
REMONUMENTATION  
8342**

ROSCOMMON COUNTY REMONUMENTATION TO BE FILED IN LIBER 3 OF LAND

APR 24 1995 **LAND CORNER RECORDATION CERTIFICATE**

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

CORNERS

**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon  
(County)

Located In:

Corner Code #

14 NOV 94 3:05 P.M.

- |                                       |                         |       |
|---------------------------------------|-------------------------|-------|
| 1. Public Land Survey                 | T 22N R 3W              | J-7   |
|                                       | T _____ R _____         | _____ |
|                                       | T _____ R _____         | _____ |
|                                       | T _____ R _____         | _____ |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____ | _____ |
|                                       | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____ | _____ |
|                                       | S _____ T _____ R _____ | _____ |

ROBERT W. SMITH  
REGISTERED OF DEEDS  
**ROSCOMMON COUNTY**  
**PEER GROUP APPROVAL**  
DATE 11-10-94 MEM

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Larry L. Cavanagh, in a field survey on October, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- |  |   |  |
|--|---|--|
| Elm Post set by William A. Burt 1849                                       | 1946 George D. Henning, Recorded Plat                 | (1980) LCRC, Cavanagh                              |
| B. Ash 7" N33°E 14 links   | 1st Addition to Plat of Pine Oaks                     | Fd Conc Monument                                   |
| Elm 12" South 21 links   | Liber 3, Page 17                                      | 1/2" bar 1.0 North (believed to be traverse point) |
|  | Set conc Mon in corner as Orig. Position of 1/4 Post. | Spike in E. Face F. Post N26°W 2.27'               |
| 1944 G. D. Henning, Fd iron (original) corner as set from G.I.O. Witnesses |   | 6" Tw. Maple N80°E 11.25'                          |
| DeLaMater 1925   | LCRC-Liber 2, Page 229                                | 4" Ash (clump) S10°W 26.67'                        |
| Elm 20" S2E 32.0   | iron in corner (same Wit)                             |  |
| W. Oak 4" North 28.0   |   | (1984), L. Cavanagh Survey, Liber 466, Page 188-96 |
|  |   | Fd. Concrete Monument                              |
|  |   | Spike in E. Face F. Post N26°W 2.27'               |
|  |   | 6" Tw. Maple N80°E 11.25'                          |
|  |   | 4" Ash (clump) S10°W 26.67'                        |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


- Found Concrete Monument  
1/2" Bar North 1.0'  
Fence Post Witness still there, but tipped over.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Set 2 1/2" x 24" Cast Iron Roscommon County Monument  
Stamped 17614-1994  
North 1/2" Bar 1.0 feet  
S89°W Nail and Tag in 8" Twin Maple 132.13 feet  
S43°W Nail and Tag in 5" Maple 130.6 feet  
East carsonite Post 1.90 feet

Is accepted as a perpetuation of the original government corner.

Signed by Larry L. Cavanagh Date 11/19  
Surveyor's Michigan License No. 17614



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983