

SURVEY & REMONUMENTATION

OCT 05 1998

3912

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in Roscommon County

Located in: Corner Code #

1. Public Land Survey T22N R3W J-9

STATE OF MICHIGAN ROSCOMMON COUNTY RECORDED 19 MAY 98 11:12 A.M. ROBERT W. SMITH REGISTER OF DEEDS FILE IN LIBER 3 OF LAND CORNERS Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration

WILLIAM A. BURT 1849 LARRY L. CAVANAGH RLS 17614 1979 SET POST CORNER SET 1/2" X 18" STEEL BAR S. PINE 7 N4E 15 4" J. PINE S35°N 17.5' S. PINE 4 S25E 8 8" B. OAK S62°W 37.86' 5" TW MAPLE N52°W 61.90' 5" MAPLE N62°E 47.77'

DNR 1930'S ESTABLISHED CORNER NO NEW BEARINGS LARRY L. CAVANAGH, LCRC, 1979 LI P 195 1/2" BAR

LCRC 1970'S L2, P238 1/2" BAR 4" J. PINE S35°W 17.5' 8" B. OAK S62°W 37.86' 5" TW MAPLE N52°W 61.94' 6" MAPLE N62°E 47.17' LI, P142 (N 1/4 COR) 8" OAK S20E 41.82 6" MAPLE N30E 49.58 LARRY L. CAVANAGH 17614 1979 RECORDED SURVEY L377, P235-263 NO WITNESSES

Grid table with columns A-L and rows 1-12. A dot is marked at the intersection of column J and row 9.

LARRY L. CAVANAGH 17614 1995 1/2" STEEL BAR SAME WITNESSES AS ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" BAR 8" TW MAPLE N52°W 61.94'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614 WT: NAIL & TAG IN 8" TW MAPLE N52°W 61.94' NAIL & TAG IN 15' R. OAK N40°E 61.51' NAIL & TAG IN 22' W. PINE S40°W 31.38' NAIL & TAG IN 3' BALSAM S30°E 25.05' CARSONITE POST N53°E 33.42'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

ROSCOMMON COUNTY PEER GROUP APPROVAL DATE MAY 15th 1998

Marvin E. Myers, P.S. County Surveyor



Signed by Larry L. Cavanagh Surveyor's Michigan License NO. 17614

Date May 16, 1998

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983