

3900

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in
Roscommon County

19 MAY 98 11:10 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

1. Public Land Survey

| | |
|-------------|---------------|
| Located in: | Corner Code # |
| T22N R3W | J-13 |
| T21N R3W | J-1 |
| T R | |
| T R | |

FILE IN LIBER 3 OF LAND CORNER
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |

A. Description of original monument and accessories and/or subsequent restoration:

| | |
|-----------------------------|-----------------------------|
| JOHN BRINK 1838 | LCRC 1970'S, L2, P250 |
| SET POST | 1/2" BAR |
| WHITE PINE 10 N59W 38 | 7" B. OAK N45W 28.9' |
| PITCH PINE 10 N4E 8 | 14" B. OAK S20W 25.3' |
| DNR 1930'S | LARRY L. CAVANAGH 1974 |
| FOUND U.S. BEARINGS | SECTION SUB-DIVISION SURVEY |
| NO TREES FOR N.B.T. | SET 1/2" X 18" STEEL BAR |
| SCHAAF INDICATES STAKE | SAME WITNESSES AS ABOVE |
| SET IN PREPARATION FOR IRON | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 18" STEEL BAR
FOUND 14" B. OAK S20W 25.3'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614
WIT: NAIL & TAG IN 14" B. OAK S32°E 23.85'
NAIL & TAG IN 9" NORWAY S20°W 25.64'
NAIL & TAG IN 8" NORWAY N45°E 59.11'
NAIL & TAG IN 13" NORWAY S38°E 77.04'
CARSONITE POST N21°W 23.47'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. SURVEY & REMONUMENTATION

OCT 05 1998

SECTION

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE MAY 15 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh*
Surveyor's Michigan License NO. 17614

Date MAY 16, 1998

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 511