

**SURVEY &  
REMONUMENTATION**

8332

APR 24 1995

ROSCOMMON COUNTY REMONUMENTATION TO BE FILED IN LIBER 3 OF LAND CORNERS

**LAND CORNER RECORDATION CERTIFICATE**  
**COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in

<u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>3W</u>	<u>K-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

14 NOV 94 3:03 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

**ROSCOMMON COUNTY  
PEER GROUP APPROVAL**

DATE 11-10-94  
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey on October, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

Y. Pine post, set by William A. Burt 1849	Liber 270, Page 173, Henning 1973
Aspen 6" S25°W 18 links	called pipe, no witnesses
Aspen 7" N60°E 26 links	
Norm Caldwell, 1963, MSHD card	LCRC Liber 2, page 227
Found 3/4" pipe	same as 1963
S55°E 51.68' 8" Oak	1978, 1981, 1991 surveys by Cavanagh
N40°W 30.18' 7" Oak	same witnesses as above
Due N 64.50' 8" Oak	

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No original evidence found  
Found 3/4" pipe in corner (Henning cap)  
7" Oak N40°W 30.18 (now 12")

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 2 1/2" x 24" cast iron Roscommon County Monument in pavement box stamped 17614-1994  
N40°W nail and tag in 12" Oak 30.19'  
S55°E nail and tag in 10" Oak 43.81'  
S10°E nail and tag in 12" Oak 13.62'  
N66°E nail and tag in 24" Oak 16.20'

Is accepted as the best available evidence of the position of the original corner.

Signed by Larry L. Cavanagh Date 11/14/94  
Surveyor's Michigan License No. 17614



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

**LIBER 3 PAGE 113**