

SURVEY & REMONUMENTATION

OCT 05 1998

SECTION

3913

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in
Roscommon County

19 MAY 98 11:12 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

	Located in:	Corner Code #
1. Public Land Survey	T22N R3W	K-9
	T_____R_____	_____
	T_____R_____	_____
	T_____R_____	_____

FILE IN LIBER 3 OF LAND CORNER
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	6	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration

WILLIAM A. BURT 1849 SET POST CORNER CEDAR 8 S44E 22 CEDAR 10 N57W 35	LCRC, LARRY L. CAVANAGH, 1978, L1, P195 1/2" STEEL BAR SAME WITNESSES AS ABOVE
DNR 1930'S FOUND U.S. BEARINGS N.B.T. SPRUCE PINE 9 S56 1/2E 98' SPRUCE PINE 6 N54 1/2W 62'	LARRY L. CAVANAGH, 17614 1979 RECORDED SURVEY L377 P 235-263 NO WITNESSES
LCRC 1970'S L2, -234 1/2" BAR HUB N4°E 13.35' HUB EAST 23.0' HUB SOUTH 12.8'	LARRY L. CAVANAGH 17614 1995 SAME WITNESSES AS ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" BAR AND FOUND HUB SOUTH 12.8'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614
WIT: HUB SOUTH 12.8'
1/2" BAR S57°E 8.37'
NAIL & TAG IN 10' W. PINE WEST 133.64'
CARSONITE POST NORTH 0.11'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE MAY 15 1998

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor



Signed by Larry L. Cavanagh
Surveyor's Michigan License NO. 17614

Date MAY 16, 1998

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983