

SURVEY & REMONUMENTATION

OCT 05 1998

SECTION

3914

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in Roscommon County

Located in: Corner Code #

1. Public Land Survey

T22N R3W L-9
T R
T R
T R

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

19 MAY 98 11:12 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNER
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration

WILLIAM A. BURT 1849
SET POST CORNER
W. PINE 15 S66E 14
MAPLE 6 N55W 14
DNR 1930'S
ESTABLISHED CORNERS
NO NEW BEARINGS

LCRC, LARRY L. CAVANAGH, 1978, L1, P196
1/2" BAR
SAME WITNESSES AS ABOVE
LARRY L. CAVANAGH, 17614 1979
RECORDED SURVEY L 377 P 235-263
NO WITNESSES

LARRY L. CAVANAGH 17614 1992
SAME WITNESSES AS ABOVE

LCRC 1970'S L2, P239
1/2" BAR
4" W. OAK S67°W 31.15'
7" POPULAR N76°W 26.33'
16" W. OAK S22°W 24.91'
6" W. OAK S58°W 28.77'

Grid table with columns A-N and rows 2-12. Cell (9, K) contains a black dot.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NOT FOUND
RESET CORNER FROM PARCEL CORNERS SURVEY RECORDED IN LIBER 377, PAGES 235-263 MID-WAY AND ON LINE BETWEEN SECTION CORNERS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614
WIT: NAIL & TAG IN 7" W. OAK S60°W 32.38'
NAIL & TAG IN 6" W. OAK N51°W 24.51'
NAIL & TAG IN 5" W. OAK N10°W 18.32'
NAIL & TAG IN 2" MAPLE S 6°W 29.67'
CARSONITE POST NORTH 0.63

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE MAY 15th 1998

Marvin E. Myers, P.S.
County Surveyor



Signed by [Signature] Date MAY 16, 1998
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983