

**SURVEY & REMONUMENTATION**

MAY 28 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 ROSCOMMON COUNTY  
 RECORDED

26 SEP 96 3:35 P.M.

For corners in Roscommon (County) Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 22N R 3W M-4  
 T 22N R 2W A-4  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

ROBERT W. SMITH  
 REGISTER OF DEEDS

**TO BE FILED IN LIBER 3 OF LAND CORNERS**  
**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Larry L. Cavanagh, in a field survey on August, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**


**A. Description of original monument and accessories and/or subsequent restoration:**

GLO J. Brink 1936 Mon - set post Wit - Aspen 8" S59 1/2W 14 lks Aspen 8" N62 1/2W 13 lks	N. Caldwell 1963 Mon - fd 4"x4" Oak post set 5/8" bar - new post Wit - S25°W 87.82' 16" N. Pine S86°E 42.53' 22" N. Pine N72°W 30.56' 8" N. Pine	L. Cavanagh, Certificate of Survey Liber 723, Page 110, 1996 Mon - fd 3/4" x 23" iron rod Wit: 5" Maple in clump N18°E 30.27' 9" N. Pine N70°W 30.61' 4" W. Pine S7°W 4.35' 14" Maple in clump S10°E 28.63' 23" N. Pine S81°E 42.58' carsonite post 1.52' West
G. Henning, Co. survey record 1941 Mon - 4"x4" post Wit - none	Liber 2, Page 227 LCRC Mon - iron bar Wit - same as Caldwell	

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Fd. 3/4" x 23" iron rod  
 8" N. Pine (now 9") NW  
 22" N. Pine (now 23") SE  
 Fd to be 2649.81' South of NE corner within 0.1' of mid-point

**ROSCOMMON COUNTY**  
**PEER GROUP APPROVAL**

DATE Sept 16, 1996  
  
 Marvin E. Myers, P.S.  
 County Surveyor

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

The best available evidence of the position of the Original Corner.  
 Set standard Roscommon County Monument stamped 1996 #17614  
 Wit - Nail and tags in  
 5" Maple in clump N18°E 30.27'  
 9" N. Pine N70°W 30.61'  
 4" W. Pine S7°W 4.35'  
 14" Maple in clump S10°E 28.63'  
 23" N. Pine S81°E 42.58'  
 Carsonite Post 1.52' West



Signed by Larry L. Cavanagh  
 Surveyor's Michigan License No. 17614

Date 9-16-96

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

*LIBER 3 PAGE 314*