

3904

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in
Roscommon County

19 MAY 98 11:10 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

1. Public Land Survey

Located in:	Corner Code #
T22N R3W	M-12 ✓
T22N R2W	A-12
T R	
T R	

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

FILE IN LIBER 3 OF LAND CORNER
Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration

JOHN BRINK 1838 SET POST CORNER SPRUCE 6 S86 1/2W 16 SPRUCE 8 N50 1/2W 30	LCRC 1970'S, L2 P251 DNR 1" PIPE 5' W. PINE N61W 12.6 6' W. PINE N88E 58.3
DNR 1930'S SET POST AT EQUAL SUB-DIVISION NO TREES	KENNETH J. OSTLING, LCRC, 1974 L1, P107 SET 1" PIPE WITNESSES SAME AS ABOVE
SCHAAF INDICATES STAKE SET IN PREPARATION FOR IRON	

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO ORIGINAL EVIDENCE
FOUND 1' X 3' PIPE (NO CAP)
3" SQUARE WOOD POST (LEFT) JUST NW OF PIPE
BOTH 1974 WITNESSES

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614
WT: NAIL & TAG IN 8' W. PINE S30°W 6.68'
NAIL & TAG IN 7' W. PINE N15°E 17.00'
NAIL & TAG IN 12' W. PINE N61°W 12.60'
NAIL & TAG IN 14' W. PINE N88°E 58.30'
CARSONITE POST WEST 0.35'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

SURVEY &
REMONUMENTATION

OCT 05 1998

SECTION

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE May 15th 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh* Date May 16, 1998
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 515