

REMONUMENTATION

5759

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 22N R 3W E-6
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Seg #3

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

15 AUG 96 10:47 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|---|----|---|----|---|----|---|----|---|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | | |
| 13 | | | | | | | | | | | | |

I, J. Dean Geers, in a field survey on October, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

See filed Remonumentation Dossier for corner and LCRC Liber 3, Page 18

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Roscommon County std. mon. in mon. box 1.5 feet North of centerline of M-55 as recorded in Liber 3, Page 18.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Std. Roscommon County mon. in mon. box

- S 35° E - 44.07 - Set Nail in Power Pole
- S 37° W - 58.95 - Set Nail in Guard Post
- N 04° E - 63.88 - Southeast Corner Building
- N 38° E - 36.25 - Center of Michcon Man Hole

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 8-8-1996

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed _____ Date 7-22-96
Surveyor's Michigan License No. 33977



Liber 3 Page 210