

**SURVEY &
REMONUMENTATION**

9539

APR 07 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in

SECTION

29 DEC 97 3:48 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File
Number

<u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Sec. 31 T 23 NR 4 W	<u>C-13</u>
	Sec. 6 T 22 NR 4 W	<u>C-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Marvin E. Myers, in a field survey on December 12, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- G.L.O. J. Brink, D.S. Nov 1839
Mon - Post in Swamp 18" deep
Wit: No witnesses near
 - GLO A. Curtis, D.S. Sept 1852
Mon - Post
Wit: 14" Y. Pine S11 1/4°W 11.25 lks
14" Y. Pine S00°12'E 11.35 lks
 - MDOT plans Job# 15911A
FRR # 72021 & FRR 68033
Sta 941+81.82 County line
Sta 996+40.07 Sec. Cor.
(5458.25 difference in sta)
Mon - Boat Spike in Monument Box
Wit: None given
 - July 11, 1919 Beuthlien, Missaukee Co.
Surveyor (prior to construction of M-55?)
Profile notes Sta 36+31 County line
Sta 64+64 1/4 Corner (2833')
Sta 91+9 Sec. Cor (2645)
Mon - None given
Wit: None given
 - Nov 1968 G. D. Henning, R.L.S.
Mon - Iron pavement box in corner
Wit: Iron pavement box in corner East 5280
 - L. 2, P. 426
Mon - Monument box in M-55

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

L. 253 P. 615 L.L. Cavanagh, R.L.S.
May 19, 1971
Mon - Pavement Box

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 12" Cabin Pin over top of a Grader Blade in pavement monument box. Measured to corners of record N89°42'26"W 5459.36 and S89°44'53"E 5279.62. Accepted position as the best available evidence of the position of the Original corner. Drove Grader Blade down to 24" below surface set Standard Roscommon County monument in Pavement Monument Box over top of grader Blade.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Mon - Standard Roscommon County Monument in pavement box.
Wit: Nail & tag in East side 5' above ground Utility Pole S22°E 98.70'
South Edge of Reflector Post N67°W 74.75'
Carsonite Post in edge of Swamp S07°W 38.9'
Carsonite post at water's edge of ditch N09°E 33.2'



**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE DEC 22, 1997**

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date *Dec 22, 1997*