

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APR 07 1998

For corners in

<u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Sec. 31 T <u>23</u> NR <u>4W</u>	<u>D-13</u>
	Sec. 6 T <u>22</u> NR <u>4W</u>	<u>D-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

SECTION STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED
29 DEC 97 3:48 P.M.
ROBERT W. SMITH
REGISTER OF DEEDS
FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on December 12, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. J. Brink, D.S. 1839
Mon - Post in Swamp to wet To mound 16" deep
Wit: No witnesses near
July 11, 1919 Beuthien, Missaukee Co. Surveyor (prior to construction of M-55?)
Profile notes Sta 36+31 County line
Sta 64+64 1/4 Corner (2833')
Sta 91+9 Sec Cor (2645')
Sta 117+60 1/4 Cor (2651')
Sta 130+35 1/8 cor (1325')
Mon - None given
Wit: None given

MDOT plans Job# 15911A
FRR # 72021 & FRR 68033
Sta 941+81.82 County line
Sta 996+40.07 Sec. Cor. (5458.25)
Sta 1049+19.00 Sec. Cor. (5278.93)
Mon - No Monument indicated
Wit: None given

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	5			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

Nov 1968 G.D. Henning, R.L.S.
Mon - Computed Position
Wit: Iron pavement box East 2640
Iron pavement box West 2640

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No monument or witnesses trees in the vicinity were found. Measured between existing monuments (5278.93)
Reestablishment of the position of the Government corner by proportional measure East 2639.47 (2640 GLO)
West 2639.46 (2640 GLO) Set Standard Roscommon County monument in Pavement Monument Box.

Accepted as a careful and faithful establishment of the position of the Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Mon - Standard Roscommon County Monument in pavement box.
Wit: Nail & tag in East side (6± above ground) Utility Pole S43°W 106.16'
North edge of reflector post N85°E 99.00'
Carsonite Post S05°W in Swamp 43.35'
Carsonite post at water's edge of ditch N06°E 38.1'



ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE DEC 22, 1997
Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by Marvin E. Myers Date DEC 22, 1997
Surveyor's Michigan License No. 31600

LIBER 3 PAGE 489