

ROSCOMMON COUNTY REMONUMENTATION

FEB 16 1994
9082
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 21 10 51 AM '93

For corners in

ROSCOMMON (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>4W</u>	<u>E-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Robert L. Lapham
REGISTERED
**ROSCOMMON COUNTY
PEER GROUP APPROVAL**
DATE 11/30/93

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, TIMOTHY L. LAPHAM, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-3: 1852, A.CURTIS, POST, BEECH 7" N20W 12L, BEECH 6" S50E 16L;
DATE UNKNOWN, SURVEYOR UNKNOWN, LCRC 2-260, CORNER MATERIAL, 3 WITS;
11/29/1973, SPICER, LCRC 1-91, COR MAT, 4 WITS;
7/1978, L.CAVANAGH, LCRC 1-125, COR MAT, 3 WITS;
8/26/1988, L.CAVANAGH, SURVEY 535-683, COR MAT, 3 WITS;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-3: FOUND 1/2" X 24" REROD WITH CAP (NOT LEGIBLE)
8" TW BIRCH N80W 24.91'
8" BIRCH WEST 24.65' (SAME AS ABOVE BEARING OFF)
ACCEPTED FOUND CORNER AS BEST EVIDENCE OF POSITION OF ORIGINAL CORNER.
THIS CORNER ESTABLISHED IN ROSCOMMON COUNTY REMONUMENTATION PROGRAM.
SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-3: SET 2" X 21" CAST IRON MONUMENT WITH BRASS ROSCOMMON COUNTY PLATE
AZ 0° 32'+/- CENTERLINE TRAIL ROAD E-W
AZ 90° 10'+/- CENTER LINE TRAIL ROAD SOUTH
AZ 180° 30.64' SET SPIKE & TAG W FACE UTILITY POLE
AZ 88° 76.67' SPIKE & TAG N FACE 15" POPLAR
AZ 356° 82.19' SPIKE & TAG W FACE 10" POPLAR
AZ 270° 0.7' CARSONITE SURVEY MARKER POST
AZ 279° 24.57' SPIKE IN S FACE 9" TWIN BIRCH



Signed by *Timothy L. Lapham* Date 12/20/93

Surveyor's Michigan License No. 27595

Date 11/30/93 Peer Group Approved
LIBER 3 PAGE 46