

9061

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Dec 21 10 50 AM '93

For corners in

<u>ROSCOMMON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>4W</u>	<u>F-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTERED

**ROSCOMMON COUNTY
PEER GROUP APPROVAL**

DATE 11/30/93

TO BE FILED IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

I, TIMOTHY L. LAPHAM, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

F-3: 1852, A.CURTIS, POST, BEECH 8" N40W 23LKS, BEECH 12" S5E 33LKS; DATE UNKNOWN, SURVEYOR UNKNOWN, LCRC 2-260, CORNER MATERIAL, 4 WITS; 12/1/1972, R.OSTLING, SURVEY 269-470, COR MAT, 3 WITS; 3/23/1972, R.OSTLING, LCRC 1-35, COR MAT, 3 WITS; 3/31/1972, R.OSTLING, SURVEY 259-487, COR MAT, 3 WITS; 11/24/1973, SPICER, LCRC 1-93, COR MAT, 4 WITS; 7/1978, L.CAVANAGH, LCRC 1-125, COR MAT, 4 WITS; 9/4/1979, L.CAVANAGH, LCRC 1-210, COR MAT, 6 WITS; 8/26/1988, L.CAVANAGH, SURVEY 535-685, COR MAT, 4 WITS; 5/25/1990, MYERS, SURVEY 575-182, COR MAT, 1 WIT; 10/2/1991, L.CAVANAGH, SURVEY 602-310, COR MAT 2 WITS;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-3: FOUND 1/2" X 20" REROD IN C/L ROAD E-W @ FENCE SOUTH
N42W 61.25' 7" CHERRY
NORTH 64.97' 5" CHERRY
SPIKE & TAG E ROOT TRIP 8" MAPLE S5E 60.10'
ACCEPTED FOUND CORNER AS BEST EVIDENCE OF POSITION OF ORIGINAL CORNER.
THIS CORNER ESTABLISHED IN ROSCOMMON COUNTY REMONUMENTATION PROGRAM.
SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3: SET 2"X21" CAST IRON MONUMENT WITH BRASS ROSCOMMON COUNTY PLATE
AZ 172° 60.24' SPIKE IN EAST ROOT OF TWIN 12" MAPLE
AZ 41° 55.66' SPIKE & TAG NW FACE 10" TRIP MAPLE
AZ 329° 53.53' SPIKE & TAG SW FACE 8" TRIP MAPLE
AZ 189° 42.65' SPIKE & TAG E FACE OF SOUTH 13" TW. POPLAR



Signed by [Signature] Date 12/20/93

Surveyor's Michigan License No. 27595

Date 11/30/93 Peer Group Approved

LIBER **3** PAGE **25**